

Pipe

rev. 24-08-2022



DECORATIVO - Wall

Indoor wall mounted projector with integrated LED sources, in-built switch and direct light emission



 Installation
 Wall

 Guarantee
 5 years

 Gross weight
 0.47 kg

 Volume
 0.000945 m³




Net weight0.4 kgInsulation classIIProtection indexIP20Operating temperature $0^{\circ} \sim +40 \, ^{\circ}\text{C}$

DimmerNon-dimmable, On-OffPower output220-240 V AC 50/60 Hz

Power supply In-built, included

YES (by qualified operators only), electronic



Source info

Integrated source Integrated LED module

Repleaceable source YES (by qualified operators only)

Power LED 7W
Emission Direct
Max consuption max 7 W

Features LED COB CREE

CCT 3000 K Duration LED (t. 25°c) 20000 h CRI > 80 **SDCM** 3 Light beam 30° Light beam flux 580 lm Useful light flux 400 lm Photobiological risk 1 Standby power < 0.50